

**Budowa dróg na osiedlu „Raciborki” w Szczecinku - etap I****TABELA ROBÓT ZIEMNYCH**ul. Obrońców Westerplatte i Szarych Szeregów**Tab.2a**

			średnie			objętość		objętość narastająco	
km	wykop	nasyp	wykop	nasyp	odległość	wykop	nasyp	wykop	nasyp
[m]	[m2]	[m2]	[m2]	[m2]	[m]	[m3]	[m3]	[m3]	[m3]
<b>0+000</b>	1.30	0.24	0.65	0.12					
<b>0+020</b>	0.38	0.48	0.84	0.36	20.00	16.80	7.20	16.80	7.20
<b>0+040</b>	1.43	0.28	0.91	0.38	20.00	18.10	7.60	34.90	14.80
<b>0+060</b>	1.29	0.21	1.36	0.25	20.00	27.20	4.90	62.10	19.70
<b>0+080</b>	1.38	0.35	1.34	0.28	20.00	26.70	5.60	88.80	25.30
<b>0+100</b>	1.13	0.21	1.26	0.28	20.00	25.10	5.60	113.90	30.90
<b>0+120</b>	0.93	0.48	1.03	0.35	20.00	20.60	6.90	134.50	37.80
<b>0+140</b>	0.80	0.28	0.87	0.38	20.00	17.30	7.60	151.80	45.40
<b>0+160</b>	0.47	0.48	0.64	0.38	20.00	12.70	7.60	164.50	53.00
<b>0+180</b>	0.49	0.62	0.48	0.55	20.00	9.60	11.00	174.10	64.00
<b>0+200</b>	1.26	0.23	0.88	0.43	20.00	17.50	8.50	191.60	72.50
<b>0+220</b>	1.73	0.15	1.50	0.19	20.00	29.90	3.80	221.50	76.30
<b>0+240</b>	1.40	0.15	1.57	0.15	20.00	31.30	3.00	252.80	79.30
<b>0+260</b>	1.21	0.35	1.31	0.25	20.00	26.10	5.00	278.90	84.30
<b>0+280</b>	1.25	0.27	1.23	0.31	20.00	24.60	6.20	303.50	90.50
<b>0+300</b>	1.38	0.22	1.32	0.25	20.00	26.30	4.90	329.80	95.40
<b>0+320</b>	1.37	0.17	1.38	0.20	20.00	27.50	3.90	357.30	99.30
<b>0+340</b>	1.58	0.15	1.48	0.16	20.00	29.50	3.20	386.80	102.50
<b>0+360</b>	1.40	0.21	1.49	0.18	20.00	29.80	3.60	416.60	106.10
<b>0+380</b>	1.38	0.27	1.39	0.24	20.00	27.80	4.80	444.40	110.90
<b>0+400</b>	1.26	0.37	1.32	0.32	20.00	26.40	6.40	470.80	117.30
<b>0+420</b>	1.42	0.37	1.34	0.37	20.00	26.80	7.40	497.60	124.70
<b>0+440</b>	1.71	0.38	1.57	0.38	20.00	31.30	7.50	528.90	132.20
<b>0+460</b>	1.48	0.13	1.60	0.26	20.00	31.90	5.10	560.80	137.30
<b>0+480</b>	1.29	0.29	1.39	0.21	20.00	27.70	4.20	588.50	141.50
<b>0+500</b>	2.07	0.19	1.68	0.24	20.00	33.60	4.80	622.10	146.30
<b>0+520</b>	0.94	0.38	1.51	0.29	20.00	30.10	5.70	652.20	152.00
<b>0+540</b>	1.48	0.30	1.21	0.34	20.00	24.20	6.80	676.40	158.80
<b>0+560</b>	1.36	0.29	1.42	0.30	20.00	28.40	5.90	704.80	164.70
<b>0+580</b>	0.18	1.10	0.77	0.70	20.00	15.40	13.90	720.20	178.60
<b>0+600</b>	0.89	0.47	0.54	0.79	20.00	10.70	15.70	730.90	194.30
<b>0+620</b>	1.16	0.36	1.03	0.42	20.00	20.50	8.30	751.40	202.60
<b>0+640</b>	1.33	0.20	1.25	0.28	20.00	24.90	5.60	776.30	208.20
<b>0+660</b>	1.31	0.24	1.32	0.22	20.00	26.40	4.40	802.70	212.60
<b>0+680</b>	1.01	0.25	1.16	0.25	20.00	23.20	4.90	825.90	217.50
<b>0+700</b>	0.72	0.47	0.87	0.36	20.00	17.30	7.20	843.20	224.70
<b>0+720</b>	2.16	0.30	1.44	0.39	20.00	28.80	7.70	872.00	232.40
<b>0+727</b>	2.16	0.30	2.16	0.30	7.00	15.12	2.10	887.12	234.50
						<b><i>Razem:</i></b>		<b>887.12</b>	<b>234.50</b>

**Budowa dróg na osiedlu „Raciborki” w Szczecinku - etap I****TABELA ROBÓT ZIEMNYCH**

ul. Boczna

**Tab.2b**

km	wykop	nasyp	średnie		odległość	objętość		objętość narastająco	
			wykop	nasyp		wykop	nasyp	wykop	nasyp
[m]	[m2]	[m2]	[m2]	[m2]	[m]	[m3]	[m3]	[m3]	[m3]
<b>0+000</b>	1.17	0.43	0.59	0.22					
<b>0+020</b>	1.67	0.21	1.42	0.32	20.00	28.40	6.40	28.40	6.40
<b>0+040</b>	1.55	0.25	1.61	0.23	20.00	32.20	4.60	60.60	11.00
<b>0+060</b>	1.43	0.32	1.49	0.29	20.00	29.80	5.70	90.40	16.70
<b>0+080</b>	1.41	0.23	1.42	0.28	20.00	28.40	5.50	118.80	22.20
<b>0+100</b>	1.37	0.25	1.39	0.24	20.00	27.80	4.80	146.60	27.00
<b>0+120</b>	1.23	0.26	1.30	0.26	20.00	26.00	5.10	172.60	32.10
<b>0+140</b>	1.29	0.26	1.26	0.26	20.00	25.20	5.20	197.80	37.30
<b>0+160</b>	1.11	0.36	1.20	0.31	20.00	24.00	6.20	221.80	43.50
<b>0+180</b>	1.47	0.21	1.29	0.29	20.00	25.80	5.70	247.60	49.20
<b>0+200</b>	1.65	0.13	1.56	0.17	20.00	31.20	3.40	278.80	52.60
<b>0+220</b>	1.57	0.15	1.61	0.14	20.00	32.20	2.80	311.00	55.40
<b>0+240</b>	1.70	0.18	1.64	0.17	20.00	32.70	3.30	343.70	58.70
<b>0+260</b>	1.37	0.37	1.54	0.28	20.00	30.70	5.50	374.40	64.20
<b>0+280</b>	1.39	0.34	1.38	0.36	20.00	27.60	7.10	402.00	71.30
<b>0+300</b>	1.27	0.43	1.33	0.39	20.00	26.60	7.70	428.60	79.00
<b>0+320</b>	1.15	0.35	1.21	0.39	20.00	24.20	7.80	452.80	86.80
<b>0+340</b>	1.39	0.28	1.27	0.32	20.00	25.40	6.30	478.20	93.10
<b>0+360</b>	1.09	0.42	1.24	0.35	20.00	24.80	7.00	503.00	100.10
<b>0+380</b>	1.36	0.38	1.23	0.40	20.00	24.50	8.00	527.50	108.10
<b>0+400</b>	0.92	0.45	1.14	0.42	20.00	22.80	8.30	550.30	116.40
<b>0+420</b>	1.15	0.32	1.04	0.39	20.00	20.70	7.70	571.00	124.10
<b>0+440</b>	1.30	0.55	1.23	0.44	20.00	24.50	8.70	595.50	132.80
<b>0+460</b>	0.95	0.86	1.13	0.71	20.00	22.50	14.10	618.00	146.90
<b>0+480</b>	0.97	0.93	0.96	0.90	20.00	19.20	17.90	637.20	164.80
<b>0+500</b>	1.26	0.89	1.12	0.91	20.00	22.30	18.20	659.50	183.00
<b>0+520</b>	1.67	0.17	1.47	0.53	20.00	29.30	10.60	688.80	193.60
<b>0+540</b>	1.60	0.10	1.64	0.14	20.00	32.70	2.70	721.50	196.30
<b>0+560</b>	1.16	0.25	1.38	0.18	20.00	27.60	3.50	749.10	199.80
<b>0+580</b>	1.18	0.28	1.17	0.27	20.00	23.40	5.30	772.50	205.10
<b>0+600</b>	0.82	0.75	1.00	0.52	20.00	20.00	10.30	792.50	215.40
<b>0+620</b>	1.11	0.46	0.97	0.61	20.00	19.30	12.10	811.80	227.50
<b>0+640</b>	1.09	0.33	1.10	0.40	20.00	22.00	7.90	833.80	235.40
<b><i>Razem:</i></b>								<b><i>833.80</i></b>	<b><i>235.40</i></b>

**Suma wykopów: 887.12+833.80=1720.92m3****Suma nasypów: 234.50+235.40=469.90m3**