

Budowa dróg na osiedlu „Raciborki” w Szczecinku - etap I**ROBOTY PRZYGOTOWAWCZE (ZDJĘCIE HUMUSU I DROGI GRUNTOWEJ O GRUBOŚCI 20CM)**

ul. Obrońców Westerplatte i Szarych Szeregów

Tab.3a

		średnie		powierzchnia	powierzchnia narastająco
km	wykop	wykop	odle- głość	wykop	wykop
[m]	[m]	[m]	[m]	[m2]	[m2]
0+000	8.60	4.30			
0+020	8.97	8.79	20.00	175.70	175.70
0+040	8.91	8.94	20.00	178.80	354.50
0+060	8.83	8.87	20.00	177.40	531.90
0+080	9.30	9.07	20.00	181.30	713.20
0+100	8.80	9.05	20.00	181.00	894.20
0+120	9.04	8.92	20.00	178.40	1072.60
0+140	8.66	8.85	20.00	177.00	1249.60
0+160	9.03	8.85	20.00	176.90	1426.50
0+180	9.22	9.13	20.00	182.50	1609.00
0+200	8.78	9.00	20.00	180.00	1789.00
0+220	8.88	8.83	20.00	176.60	1965.60
0+240	8.62	8.75	20.00	175.00	2140.60
0+260	8.72	8.67	20.00	173.40	2314.00
0+280	8.69	8.71	20.00	174.10	2488.10
0+300	8.60	8.65	20.00	172.90	2661.00
0+320	8.53	8.57	20.00	171.30	2832.30
0+340	8.44	8.49	20.00	169.70	3002.00
0+360	8.46	8.45	20.00	169.00	3171.00
0+380	8.72	8.59	20.00	171.80	3342.80
0+400	8.88	8.80	20.00	176.00	3518.80
0+420	8.89	8.89	20.00	177.70	3696.50
0+440	9.71	9.30	20.00	186.00	3882.50
0+460	8.70	9.21	20.00	184.10	4066.60
0+480	8.73	8.72	20.00	174.30	4240.90
0+500	9.73	9.23	20.00	184.60	4425.50
0+520	10.04	9.89	20.00	197.70	4623.20
0+540	9.90	9.97	20.00	199.40	4822.60
0+560	8.74	9.32	20.00	186.40	5009.00
0+580	9.47	9.11	20.00	182.10	5191.10
0+600	8.99	9.23	20.00	184.60	5375.70
0+620	8.82	8.91	20.00	178.10	5553.80
0+640	8.45	8.64	20.00	172.70	5726.50
0+660	8.62	8.54	20.00	170.70	5897.20
0+680	8.63	8.63	20.00	172.50	6069.70
0+700	8.88	8.76	20.00	175.10	6244.80
0+720	8.92	8.90	20.00	178.00	6422.80
0+727	8.92	8.92	7.00	62.44	6485.24
<i>Razem:</i>					<i>6485.24</i>

Budowa dróg na osiedlu „Raciborki” w Szczecinku - etap I**ROBOTY PRZYGOTOWAWCZE (ZDJĘCIE HUMUSU I DROGI GRUNTOWEJ O GRUBOŚCI 20CM)**ul. Boczna**Tab.3b**

		średnie		powierzchnia	powierzchnia narastająco
km	wykop	wykop	odle- głość	wykop	wykop
[m]	[m]	[m]	[m]	[m2]	[m2]
0+000	8.73	4.37			
0+020	8.73	8.73	20.00	174.60	174.60
0+040	8.94	8.84	20.00	176.70	351.30
0+060	8.78	8.86	20.00	177.20	528.50
0+080	8.60	8.69	20.00	173.80	702.30
0+100	8.61	8.61	20.00	172.10	874.40
0+120	8.67	8.64	20.00	172.80	1047.20
0+140	8.63	8.65	20.00	173.00	1220.20
0+160	8.74	8.69	20.00	173.70	1393.90
0+180	8.56	8.65	20.00	173.00	1566.90
0+200	8.66	8.61	20.00	172.20	1739.10
0+220	8.47	8.57	20.00	171.30	1910.40
0+240	8.71	8.59	20.00	171.80	2082.20
0+260	8.72	8.72	20.00	174.30	2256.50
0+280	8.76	8.74	20.00	174.80	2431.30
0+300	8.87	8.82	20.00	176.30	2607.60
0+320	8.78	8.83	20.00	176.50	2784.10
0+340	8.84	8.81	20.00	176.20	2960.30
0+360	8.83	8.84	20.00	176.70	3137.00
0+380	8.98	8.91	20.00	178.10	3315.10
0+400	8.95	8.97	20.00	179.30	3494.40
0+420	8.78	8.87	20.00	177.30	3671.70
0+440	8.91	8.85	20.00	176.90	3848.60
0+460	9.14	9.03	20.00	180.50	4029.10
0+480	9.37	9.26	20.00	185.10	4214.20
0+500	10.59	9.98	20.00	199.60	4413.80
0+520	8.53	9.56	20.00	191.20	4605.00
0+540	8.64	8.59	20.00	171.70	4776.70
0+560	8.64	8.64	20.00	172.80	4949.50
0+580	8.80	8.72	20.00	174.40	5123.90
0+600	9.30	9.05	20.00	181.00	5304.90
0+620	8.99	9.15	20.00	182.90	5487.80
0+640	8.78	8.89	20.00	177.70	5665.50
<i>Razem:</i>					<i>5665.50</i>

Suma: 6485.24+5665.50=12150.74m2